	Items of work (grouped under sub-heads the sub works of the estimate)
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 metres and an average l excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods con specifications.
2	Plain cement concrete 1:3:6 mix with crushed stone aggregate 40m nominal size mechanically mixed placed in fou compacted by vibration including curing for 14 days compelte as per specifications.MORTH Specification No.408
3	Providing and laying in position plain cement concrete of mix M 20 with OPC cement @300 kgs, with 20 mm and down granite metal coarse aggregates @ 0.64 cum and fine aggregates @ 0.43 cum with superplastisiser @ 3 lts confirming 1999 Reaffirmed - 2008, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundatio cills, including cost of all materials, labour HOM of machinery curing complete as per specifications.
4	Providing TMT steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, la welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete a (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specificatio
5	Providing and removing centering, shuttering, strutting, propping etc., for columns, pillars, piers, abutments, post square/rectangular/polygon in plan including cost of all materials, labour complete as per specification
6	Supplying and fixing precast rainforecd concee slab 10cm thick including cost of reinforcement as per design and drawing m transportation hire chages of machinery machine cuttingh the vertica face to get plain even surface etc., complete with all l conveyance charges labour charges inclusive of cost of all materials complete as per specification.
7	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer incharge of the work lea basic rate for Haulage of materials as per item No. 17.4/KSRRB : M1004.1 .. Rs 2.00 tonne / km b) Average earth o Tonne.km for Rs 2.00/km c) Add loading and unloading complete as per specification.

CERTIFICATE:

1 Work done is satisfactory

2 There are no departmental issuesmade to the contractor

3 The contractor has cleared all debrice from work spot